

Rad Master Quick Commissioning Manual Full Zone

Title Page

© 2001 Comeragh Controls Ltd

No part of this document may be reproduced by any process without the prior written permission from Comeragh Controls Ltd.

The information in this document is provided for reference only. While every effort has been made to make sure it is accurate and complete, Comeragh Controls Ltd does not accept any liability arising out of the application or use of the information or products described herein. Moreover, Comeragh Controls Ltd reserves the right to alter specifications or procedures without notice.

This document may contain or refer to information or products protected by copyright or patents and does not convey any license under the patent rights of Comeragh Controls Ltd nor the rights of others.

All products referred herein are trademarks of their respective owners.

Publication details:

Title: Rad Master Quick Commissioning Manual

Revision : 16.1

Issue Date: 11-12-09

Part Number: CM-QCM(V16.1)

Produced by:

Product Support Department

Comeragh Controls Ltd

Irishtown Clonmel Co. Tipperary


Ireland

IMPORTANT
Before Switching ON

CHECK
FOR ANY
ELECTRICAL
SHORTS

Check for any shorts

Use a DVM (Digital Volt Meter) and check for any shorts between A,B,G,V,
typically if there are no shorts the reading will be approx 1k Ω or greater ,
if there is a short the reading will be approx 1-10 Ω



Pass Approx. 1000 Ω or greater


Fail Approx. 1-10 Ω

Note :

- Between 24v + & - there is always a shore because this travel trough the transformer
- Detach the cable attached to 24v +and then check for a short between the 24v + cable & 24v -.

PLUMBING


- Automatic by-pass circuit fitted & tested
- The DHW valve is fitted in the direction of flow
- The system has been pressurized to check for leaks and none have been found.
- The DHW probe located $\frac{3}{4}$ down cylinder – good contact cylinder metal body



ELECTRICAL

Check for any shorts across ABGV


Boiler Relay Board



➤ Address (Jumper In) or (Dial set to 1)

➤ Boiler Relay Jumper fitted

Cylinder Relay Board




Note: If only one board fitted it must be the cylinder board because of the probe)

- Address: (Jumper Out) or (Dial Address Block set to 0) □
- Cylinder Probe attached to Cylinder Relay Board - Connector P2 □
- Cylinder Relay Board – Comms cable (ABGV), V not attached □

Mechanical Stat Attached to P1 (Top of PCB) □

Mechanical Stat set to typically 30°C □




Overview:

Heat Dump will override zone control and activate all zone outputs (open all actuators), turn off the boiler and immersions.
Not applicable in Config Mode

SENSORS

Set address □

Set Type (Relay - Set ST to 1) (No Relay - Set ST to 0) □



Overview:

Each Stat must have it's own unique zone number programmed

- Zone 1 – Default to DHW
- Zone 2-32 are for heating

Follow step indicated on the chart to program the stat


CONSOLE


➤ Set DHW BOOST on Saturday morning at 5am □



Press 1 (DHW Zone)

Press 

Display Shows DHW Schedule



Press  to move to Sat

Use the  and  buttons to move to the desired hour - 5am

Press  to select **Boost Heat**. Note  symbol will be displayed for that hour

➤ Set number of zones. (change from 32 to actual no zones) □

Press MODE and HOME keys together .

Display Shows

***4567890123456
1234567890123456

Press MODE button until


Display shows

En P1
0000

Press  until P08 is displayed

Display shows

En P8
0016

Use the numeric keypad and enter the number of zones followed by 

Press  key to exit



Note En P1- En P7 should be set to 0000



➤ Time and Date are set at the console □

Press  key .

Console Displays

Time 09:40
25/02/06 < FRI >

Move brackets press  and .



Change value press  or .

SYSTEM

➤ Set temp for each zone □

At Console


Enter zone number

Set value by pressing  or 

➤ Setup schedule for each zone □

Enter the Zone Number

Display Shows



Press 

Display shows

Use the  and  buttons to move to the desired hour

To time heat for the entire hour press 

➤ Check communication to each zone (Press Home & Mode together at console) □

Press MODE and HOME keys together .

Display Shows

***4567890123456
?234567890123456

If * display, sensor is communication with the console

If the number displayed, this sensor failed to communicated with control

➤ Ensure each zone open it's respective radiators. □

Use the advance button on the sensors to call for heat in that room

Check to see if the rad heats

Note: 3 Min delay on 1st call to boiler to allow time for the actuators to open

➤ Ensure the boiler activate 3 min after any zone call for heat. □

Check boiler is operational

SIGN OFF

Commissioning Date	
Installer	
Home Owner	